

Beco Products Ltd

5 Atherton Way
Brigg
North Lincolnshire
DN20 8AR
Tel: 01652 653844
e-mail: info@becowallform.co.uk
website: www.becowallform.co.uk



Agrément Certificate
14/5083
Product Sheet 1

BECO CONCRETE FORMWORK SYSTEMS

BECO WALLFORM INSULATING CONCRETE FORMWORK SYSTEM

This Agrément Certificate Product Sheet⁽¹⁾ relates to the Beco Wallform Insulating Concrete Formwork System, comprising expanded polystyrene (EPS) moulded elements for use in the formation of loadbearing and non-loadbearing internal, external, separating walls to provide thermal insulation in residential and commercial buildings of similar occupancy.

(1) Hereinafter referred to as 'Certificate'.

CERTIFICATION INCLUDES:

- factors relating to compliance with Building Regulations where applicable
- factors relating to additional non-regulatory information where applicable
- independently verified technical specification
- assessment criteria and technical investigations
- design considerations
- installation guidance
- regular surveillance of production
- formal three-yearly review.



KEY FACTORS ASSESSED

Structural performance — the system components have adequate strength to resist the loads associated with installation loading (see section 6).

Thermal performance — the system contributes to the overall thermal performance of the wall construction (see section 7).

Risk of condensation — walls, openings and junctions with other elements will adequately limit the risk of surface condensation (see section 8).

Behaviour in relation to fire — the concrete walls formed from the system provide fire resistance when designed in accordance with BS 8110-2 : 1985 or BS EN 1992-1-2 : 2004 (see section 9).

Sound insulation — separating and internal walls with a minimum concrete core density and detailing stated in this Certificate will provide sufficient sound resistance (see section 14).

Durability — the system components are durable (see section 16).

The BBA has awarded this Certificate to the company named above for the system described herein. This system has been assessed by the BBA as being fit for its intended use provided it is installed, used and maintained as set out in this Certificate.

On behalf of the British Board of Agrément

Date of First issue: 17 February 2014

A handwritten signature in black ink that reads 'B Chamberlain'.

Brian Chamberlain
Head of Approvals — Engineering

A handwritten signature in black ink that reads 'Claire'.

Claire Curtis-Thomas
Chief Executive

Certificate amended on 27 February 2014 to remove fax number.

The BBA is a UKAS accredited certification body — Number 113. The schedule of the current scope of accreditation for product certification is available in pdf format via the UKAS link on the BBA website at www.bbacerts.co.uk

Readers are advised to check the validity and latest issue number of this Agrément Certificate by either referring to the BBA website or contacting the BBA direct.

British Board of Agrément
Bucknalls Lane
Watford
Herts WD25 9BA

©2014

tel: 01923 665300
fax: 01923 665301
e-mail: mail@bba.star.co.uk
website: www.bbacerts.co.uk

Regulations

In the opinion of the BBA, the Beco Wallform Insulating Concrete Formwork System, if installed, used and maintained in accordance with the provisions of this Certificate, will meet or contribute to meeting the relevant requirements of the following Building Regulations (the presence of a UK map indicates that the subject is related to the Building Regulations in the region or regions of the UK depicted):



The Building Regulations 2010 (England and Wales) (as amended)

Requirement:	A1	Loading
Requirement:	A2	Ground movement
Requirement:	A3	Disproportionate collapse
Comment:	Walls formed from the system will have adequate strength and stiffness to satisfy these Requirements. See sections 6.1 to 6.4, 6.10 and 6.11 of this Certificate.	
Requirement:	B3(1)(2)(3)	Internal fire spread (structure)
Comment:	Walls formed from the system can meet this Requirement. See sections 9.2 to 9.7 of this Certificate.	
Requirement:	C2(a)	Resistance to moisture
Comment:	Walls formed from the system can adequately limit the risk of moisture ingress from the ground. See section 11.1 of this Certificate.	
Requirement:	C2(c)	Resistance to moisture
Comment:	Walls formed from the system can adequately limit the risk of surface condensation and contribute to minimising the risk of interstitial condensation. See sections 8.1 and 8.2 of this Certificate.	
Requirement:	E1	Protection against sound from other parts of the building and adjoining buildings
Requirement:	E2(a)	Protection against sound within a dwelling-house etc
Comment:	Walls formed from the system can adequately meet these Requirements. See sections 14.1 to 14.3 of this Certificate.	
Requirement:	L1(a)(i)	Conservation of fuel and power
Comment:	Walls formed from the system can contribute to a building meeting its Target Emission Rate. See sections 7.1 to 7.4, 13.1 and 13.2 of this Certificate.	
Regulation	7	Materials and workmanship
Comment:	The system elements are acceptable. See section 16 and the <i>Installation</i> part of this Certificate.	
Regulation:	26	CO ₂ emission rates for new buildings
Comment:	The system can satisfy or contribute to satisfying this Regulation. See sections 7.1 to 7.4, 13.1 and 13.2 of this Certificate.	



The Building (Scotland) Regulations 2004 (as amended)

Regulation:	8(1)	Fitness and durability of materials and workmanship
Comment:	The system can contribute to a construction meeting this Regulation. See sections 15 and 16 and the <i>Installation</i> part of this Certificate.	
Regulation:	9	Building Standards applicable to construction
Standard:	1.1(a)(b)	Structure
Standard:	1.2	Disproportionate collapse
Comment:	Walls formed from the system will have adequate strength and stiffness to satisfy this Standard, with reference to clauses 1.1.1 ⁽¹⁾⁽²⁾ to 1.1.3 ⁽¹⁾⁽²⁾ and, when suitably reinforced, clause 1.2.1 ⁽¹⁾⁽²⁾ . See sections 6.2, 6.3, 6.4, 6.10 and 6.11 of this Certificate.	
Standard:	2.2	Separation
Standard:	2.3	Structural protection
Comment:	Walls can satisfy the short, medium or long fire-resistance durations required by this Standard, with reference to clauses 2.2.1 ⁽¹⁾ , 2.2.2 ⁽¹⁾⁽²⁾ , 2.2.3 ⁽¹⁾⁽²⁾ , 2.2.5 ⁽¹⁾⁽²⁾ and 2.2.8 ⁽¹⁾ . Junctions between walls can maintain the required fire-resistance durations with reference to clauses 2.2.7 ⁽²⁾ and 2.2.10 ⁽¹⁾ . See section 9.1 of this Certificate. The expanded polystyrene component of the wall would be classified as combustible. However, the completed wall can satisfy the required durations of fire-resistance with reference to clauses 2.2.4 ⁽²⁾ and 2.2.7 ⁽¹⁾ . See sections 9.1 to 9.7 of this Certificate.	
Standard:	3.4	Moisture from the ground
Comment:	Walls formed from the system can satisfy this Standard, with reference to clauses 3.4.1 ⁽²⁾ and 3.4.5 ⁽¹⁾ . See section 11.1 of this Certificate.	
Standard:	3.15	Condensation
Comment:	Walls formed from the system can adequately limit the risk of surface condensation, with reference to clauses 3.15.1 ⁽¹⁾⁽²⁾ and 3.15.3 ⁽¹⁾ . Walls can contribute to minimising the risk of interstitial condensation, with reference to clauses 3.15.1 ⁽¹⁾ , 3.15.4 ⁽¹⁾ and 3.15.5 ⁽¹⁾⁽²⁾ . See sections 8.1 and 8.2 of this Certificate.	
Standard:	5.1	Noise separation
Standard:	5.2	Noise reduction between rooms
Comment:	Separating walls formed from the system satisfy these Standards, with reference to clauses 5.1.1 ⁽¹⁾⁽²⁾ , 5.1.2 ⁽¹⁾⁽²⁾ , 5.1.4 ⁽¹⁾⁽²⁾ , 5.1.7 ⁽²⁾ , 5.1.8 ⁽¹⁾ , 5.2.1 ⁽¹⁾⁽²⁾ and 5.2.2 ⁽¹⁾⁽²⁾ . See sections 14.1 and 14.2 of this Certificate.	

Standard:	6.1(b)	Carbon dioxide emission
Standard:	6.2	Building insulation envelope
Comment:		The system will enable, or contribute to enabling, a wall to meet these Standards, with reference to clauses 6.1.1 ⁽¹⁾⁽²⁾ , 6.1.4 ⁽¹⁾ , 6.1.5 ⁽¹⁾ , 6.2.1 ⁽¹⁾⁽²⁾ , 6.2.3 ⁽¹⁾ , 6.2.4 ⁽¹⁾⁽²⁾ , 6.2.5 ⁽¹⁾⁽²⁾ , 6.2.6 ⁽²⁾ and 6.2.7 ⁽²⁾ . See sections 7.1 to 7.4, 13.1 and 13.3 of this Certificate.
Standard:	7.1(a)(b)	Statement of sustainability
Comment:		The system can contribute to meeting the relevant Requirements of Regulation 9, Standards 1 to 6 and therefore will contribute to a construction meeting a bronze level of sustainability as defined in this Standard. In addition, the product can contribute to a construction meeting a higher level of sustainability as defined in this Standard, with reference to clauses 7.1.4 ⁽¹⁾⁽²⁾ [Aspects 1 ⁽¹⁾⁽²⁾ and 2 ⁽¹⁾], 7.1.6 ⁽¹⁾⁽²⁾ [Aspects 1 ⁽¹⁾⁽²⁾ and 2 ⁽¹⁾] and 7.1.7 ⁽¹⁾⁽²⁾ [Aspect 1 ⁽¹⁾⁽²⁾]. See sections 7.1 to 7.4 of this Certificate. (1) Technical Handbook (Domestic). (2) Technical Handbook (Non-Domestic).



The Building Regulations (Northern Ireland) 2012

Regulation:	23(a)(i)(iii)(b)	Fitness of materials and workmanship
Comment:		The system is acceptable. See section 16 and the <i>Installation</i> part of this Certificate.
Regulation:	28(a)(b)	Resistance to moisture and weather
Comment:		Walls formed from the system can adequately limit the risk of moisture ingress from the ground. See section 11.1 of this Certificate.
Regulation:	29	Condensation
Comment:		Walls formed from the system can contribute to minimising the risk of interstitial condensation. See sections 8.1 and 8.2 of this Certificate.
Regulation:	30	Stability
Comment:		Walls formed from the system will have adequate strength and stiffness to satisfy this Regulation. See sections 6.2 to 6.4, 6.10 and 6.11 of this Certificate.
Regulation:	31	Disproportionate collapse
Comment:		Walls, when suitably reinforced, will have adequate strength and stiffness to satisfy this Regulation. See sections 6.2 to 6.4, 6.10 and 6.11 of this Certificate.
Regulation:	35	Internal fire spread – Structure
Comment:		Walls formed from the system can satisfy this Regulation. See sections 9.2 to 9.7 of this Certificate.
Regulation:	39(a)(i)	Conservation measures
Regulation:	40(2)	Target carbon dioxide Emission Rate
Comment:		The system can satisfy or contribute to satisfying this Regulation. See sections 7.1 to 7.4, 13.1 and 13.2 of this Certificate.
Regulation:	49	Resistance to the passage of sound
Regulation:	50(a)(b)	Protection against sound within a dwelling or room for residential purposes
Regulation:	51	Reverberation in the common internal parts of a buildings containing flats or rooms for residential purposes
Comment:		The system can satisfy this Regulation. See sections 14.1 and 14.2 of this Certificate.

Construction (Design and Management) Regulations 2007

Construction (Design and Management) Regulations (Northern Ireland) 2007

Information in this Certificate may assist the client, CDM co-ordinator, designer and contractors to address their obligations under these Regulations.

See sections: 3 *Delivery and site handling* (3.1 and 3.4) and 17 *Installation – General* (17.2) of this Certificate.

Additional Information

NHBC Standards 2014

NHBC accepts the use of the Beco Wallform Insulating Concrete Formwork System, provided it is installed, used and maintained in accordance with this Certificate, in relation to *NHBC Standards*.

General

Beco Wallform Insulating Concrete Formwork System provides permanent formwork for in-situ dense aggregate concrete walls (reinforced or plain) and contributes to the thermal insulation of the finished construction. The system is for use in loadbearing and non-loadbearing internal, external and separating walls in residential and commercial buildings subject to structural and fire considerations and building use.

The system can also be used below ground, subject to design and supervision by a Chartered Structural Engineer and adherence to structural design to British or European Standards (see section 6.2) and detailing in accordance with BS 8102 : 2009. However, below-ground watertight construction and protection against ingress of ground water has not been assessed and is outside the scope of this Certificate. Use of the system in any structure is subject to design limitations in accordance with British or European Standards.

Technical Specification

1 Description

1.1 The Beco Wallform Insulating Concrete Formwork System consists of a range of elements (see Figure 1) moulded from expanded polystyrene (EPS) beads into inner and outer profiled panels connected by integral webs or steel wire connectors, depending on function. The elements are available in Standard, Acoustic and Firewall grades, and four system types; 250, 313, 375 and 438 (see Table 1).

Figure 1 Typical standard wall elements (EPS web and steel wire connector)










Table 1 Range of system elements

Element	Overall width (mm)	Width A	Height (mm)	Core B	Length (mm)
Standard Wallblock	250	55	250	140	750
	312.5	117.5	250	140	750/1125
	375	180	250	140	750
	438	243	250	140/200	750
Firewall block	250	55	250	140	1250
	312.5	117.5	250	140/200	1250
	375	180	250	140/200	1250
	438	243	250	140/200	1250
Acoustic block	250	55	250	140	500
	312.5	117.5	250	140	500



continued

Table 1 Range of system elements (continued)

Element	Overall width (mm)	Width &	Height (mm)	Core B	length (mm)
<i>Lintel block</i> 	250	55	250	140	Various ⁽¹⁾
	375	180	250	140	Various ⁽¹⁾
	438	243	250	140	Various ⁽¹⁾
<i>Floor edge block</i> 	250	55	250	140	1250
	375	180	250	140	1250
	438	243	250	140	1250
<i>45° Corner Block</i> 	250	55	250	140	312.5
	312.5	117.5	250	140/200	312.5
	375	180	250	140/200	312.5
	438	243	250	140/200	312.5
<i>Curved/Curved Transition Wall Block</i> 	250	55	250	140	750
	312.5	117.5	250	140	Various ⁽¹⁾
	375	180	250	140	Various ⁽¹⁾
	438	243	250	140	Various ⁽¹⁾
<i>End block</i> 	250	–	250	140	Various ⁽¹⁾
	375	–	250	140	Various ⁽¹⁾
	438	–	250	140	Various ⁽¹⁾
<i>End set</i> 	140	–	85/105	–	–

continued

Table 1 Range of system elements (continued)

Element	Overall width (mm)	Width A	Height (mm)	Core B	Length (mm)
Height adjuster	55	–	62.5	–	750
	120	–	62.5	–	750
	183	–	62.5	–	750
End piece	77.5	–	250	–	
	140	–	250	–	
	202.5	–	250	–	
	265	–	250	–	
Fire stop end piece			250		
Corbel block			250		

(1) In increments of 62.5 mm.

1.2 The elements are provided with castellated joints along the top and bottom edges and interlocking joints at vertical edges. All element faces have grooves 2.5 mm deep and 17.5 mm wide at 62.5 mm centres to provide a key for the application of plaster or render. Each element interlocks and builds, horizontally and vertically, into a tight, rigid formwork when connected together. Once connected together, the formwork enables a series of connecting concrete columns or a continuous concrete core 140 mm or 200 mm wide to be formed by pouring concrete into the formwork.

1.3 The range of elements also include; curved blocks, lintel block, floor edge block, height adjuster, end set and end piece. The Certificate holder can be contacted for further details.

1.4 The expanded polystyrene (EPS) used in the elements has the properties given in Table 2.

Table 2 EPS properties

Property	Test method	Value to BS EN 13163: 2008
Estimated thermal conductivity $\lambda_{90/90}$ value ($\text{W}\cdot\text{m}^{-1}\cdot\text{K}^{-1}$)	BS EN 12667: 2001	0.038
Compressive strength at 10% deformation ($\text{kN}\cdot\text{m}^{-2}$)	BS EN 826: 1996	150
Bending strength ($\text{kN}\cdot\text{m}^{-3}$)	BS EN 12089 : 1997	200
Density ($\text{kg}\cdot\text{m}^{-3}$)	BS EN 602 : 2004	28

1.5 The concrete infill is sourced from QSRMC⁽¹⁾-registered or a BSI-Kitemarked batching plant or supplier and must be of the specification defined in Table 3. All concrete design for above and below ground construction must be carried out to relevant British or European Standards. The Certificate holder recommends a use of pumpable grade concrete.

(1) Quality Scheme for Ready Mixed Concrete.

Table 3 Recommended concrete specification and characteristics

Characteristic (units)	Specification
unreinforced	C25/30
reinforced	C35/45
Minimum density ($\text{kg}\cdot\text{m}^{-3}$)	2200
Minimum mass ($\text{kg}\cdot\text{m}^{-2}$)	415
Slump class	S3
Target slump (mm) ⁽¹⁾	100-150
Maximum aggregate size (mm):	
Pumped	10
Free flow	<20
Minimum cement content ($\text{kg}\cdot\text{m}^{-3}$)	300
Water : cement ratio	defined by structural engineer

(1) In accordance with BS EN 206-1 : 2000 and BS EN 12350-2 : 2000.

1.6 Where admixtures are used to assist placement they should comply with BS EN 934-2 : 2001 or BS EN 480-1 : 2006.

1.7 Other components and finishes specified for use with the system but not assessed or covered by this Certificate are:

- wall foundation
- steel reinforcement — where required, should comply with BS 4449 : 2005 and sourced from a CARES (UK Certification Authority for Reinforcing Steels) registered supplier
- external masonry — may be of brickwork, or stonework fixed in accordance with the provisions of BS EN 1996-1-2 : 2005 or the appropriate part of BS 8298 : 2010 respectively
- external render — in accordance with BS EN 13914-1 : 2005 and suitable for use with the system
- acrylic render — suitable acrylic render products in accordance with BS EN 13914-1 : 2005 for use with the system
- brick slip systems — third-party certificated systems (the Certificate holder's advice should be sought)
- brickwork/stonework ties — to BS EN 845-1 : 2003
- fire barriers
- propping/support system — as recommended by the Certificate holder
- basement waterproofing membrane
- plasterboard internal linings — to BS EN 520 : 2004 and BS 8212 : 1995.

2 Manufacture

2.1 The formwork elements are manufactured from expanded polystyrene (EPS).

2.2 As part of the assessment and ongoing surveillance of product quality, the BBA has:

- agreed with the manufacturer the quality control procedures and product testing to be undertaken
- assessed and agreed the quality control operated over batches of incoming materials
- monitored the production process and verified that it is in accordance with the documented process
- evaluated the process for management of nonconformities
- checked that equipment has been properly tested and calibrated
- undertaken to carry out the above measures on a regular basis through a surveillance process, to verify that the specifications and quality control operated by the manufacturer are being maintained.

3 Delivery and site handling

3.1 Good site practice should be observed to prevent damage to the formwork elements.

3.2 The system elements are supplied to site interlocked with corner protection pieces in taped, or shrink wrapped packs. All packaged elements are clearly labelled with product type and code number, allowing full traceability of supply. The wrapping should not be opened until the contents are required.

3.3 The formwork elements must be stored in their packaging on firm, level and dry ground. If stored outside packs must be further protected from the weather using opaque plastic sheeting or tarpaulin.

3.4 Care must be taken when handling the EPS elements to avoid damage and contact with solvents or materials containing volatile organic components such as newly treated timber. The elements must not be exposed to open flame or other ignition sources.

Assessment and Technical Investigations

The following is a summary of the assessment and technical investigations carried out on the Beco Wallform Insulating Concrete Formwork System.

Design Considerations

4 Use

4.1 The Beco Wallform Insulating Concrete Formwork System is for use as permanent insulated formwork in loadbearing and non-loadbearing reinforced and unreinforced concrete external, internal and separating walls in domestic and commercial buildings, subject to design limitations regarding height, load and fire risk. Use in any structures is subject to design limitations in accordance with British or European Standards.

4.2 The system provides permanent formwork for in-situ concrete walls and contributes to the thermal insulation of the finished construction.

4.3 The system has not been assessed for use below ground, such as basement construction, where a watertight construction and resistance to hydrostatic pressure from ground water or other liquids is required. Use in this situation is therefore outside the scope of this Certificate.

4.4 The foundations are outside the scope of this Certificate but must be adequate to support the intended loads.

4.5 The system is for use with the internal and external finishes to the specification given in section 1.7 of this Certificate.

5 Practicability of installation

The system must only be installed by installers who have been trained and approved by the Certificate holder (see sections 17 and 18).

6 Structural performance

General



6.1 The system is satisfactory for use in loadbearing and non-loadbearing walls as permanent formwork for in-situ dense aggregate concrete.



6.2 Structures subject to the national Building Regulations incorporating the system should be designed to the relevant sections of BS 8007 : 1987, BS 8102 : 2009, BS 8110-1 : 1997 or BS EN 1991-1-4 : 2005, BS EN 1992-1-1 : 2004 and BS EN 1992-1-2 : 2004 and certified by a suitably qualified and experienced individual.

6.3 Other buildings not subject to any of the Regulations defined in section 6.2 should also be built in accordance with these same Standards.

6.4 The concrete is not easily examined after casting, therefore, as specified in BS 8110-1 : 1997, Section 2, or BS EN 1992-1-1 : 2004, Sections 4 and 8, care must be taken to ensure full compaction is achieved. If required, compaction may be checked by removal of a small section of the EPS element to allow observation and then securely replaced. Particular attention should be given to compaction of concrete in basement walls and areas adjacent to formed openings.

6.5 Storey-height walls using the system are normally constructed in one continuous lift (see section 17.4). Particular care is necessary to maintain alignment during concrete filling, and checking between lifts. Propping systems (see section 6.12) used in conjunction with the formwork must be checked prior to and during the concrete pour to ensure stability and alignment is maintained.

6.6 With respect of concrete placement and especially regards any use of poker vibration for compaction of wet concrete (see also section 17.5) the *Beco Wallform Insulating Concrete Formwork Technical Manual* must be consulted.

6.7 When the formwork is used to construct a watertight basement (not covered by this Certificate), an effective waterproofing should be employed, ensuring correct detailing and jointing methodology to the Certificate holder's instructions and the requirements of BS 8102 : 2009 for Types A and C basement construction.

6.8 Generally, facing brickwork or stonework should be attached using suitable wall ties that are fixed through the formwork and into the concrete core with suitable fixings (see section 1.7) to the depth recommended by the wall tie manufacturer.

6.9 Heavy attachments or finishes, fixed either internally or externally, must be attached via support systems designed to take account of the applied load using suitable fixings or plates fixed or cast into the concrete core. The EPS must not be used to support any internal or external loads.

Strength and stability



6.10 Walls constructed using the formwork may be treated as conventional unreinforced (plain) concrete or reinforced concrete walls. Particular attention should be made to the type of concrete mix used (see Table 3) to ensure segregation does not occur and the wet concrete is allowed to flow freely around formed openings and through congested areas of reinforcement.

6.11 The nominal concrete cover to reinforcement should be that appropriate to exposure classes X0 and XC1 described in BS 8500-1 : 2006, Table A.1 and BS EN 206-1 : 2000, Table 1.

6.12 To achieve a structurally stable formwork during the construction process, the formwork must be braced sufficiently to resist the loads imparted on the system by the wet concrete and other construction loads. A typical system of temporary bracing should be designed to give lateral support during the pouring of the concrete and curing stage. The Certificate holder recommends that propping is provided at maximum 1.5 metre centres, or less when openings are formed in the wall. All soffits to openings should be fully supported until the concrete has attained the minimum required strength.

7 Thermal performance



7.1 The thermal performance of each building incorporating the forms must be evaluated in accordance with the relevant national Building Regulations, and is the responsibility of the overall designer of the building.

7.2 Calculations of the thermal transmittance (U value) of a specific wall construction should be carried out in accordance with BS EN ISO 6946 : 2007 and BRE report 443 : 2006 using an estimated lambda _{90/90} value thermal conductivity of 0.038 W·m⁻¹·K⁻¹.

7.3 As an example, using the Standard Wallform 313 (117.5 mm outer face and 55 mm inner face) with 10 mm directly applied external render finish and 12.5 mm directly applied plaster internal finish, can achieve a U value of 0.206 W·m⁻²·K⁻¹. Other wall constructions that require internal and external finishes to be fixed into rails or concrete core, will affect the thermal transmittance, as will chasing into the EPS for services. Therefore, for other constructions, specific thermal calculations will need to be carried out in accordance with BS EN ISO 6946 : 2007 to determine U values.

7.4 Junctions with other elements should be designed to limit heat loss. Detailed guidance for junctions and on limiting heat loss by air infiltration can be found in:

England and Wales — Approved Documents to Part L and, for new thermal elements to existing buildings, Accredited Construction Details (version 1.0) (for new-build, see also SAP 2009, Appendix K, and the *iSBEM User Manual*)

Scotland — Accredited Construction Details⁽¹⁾

Northern Ireland — Accredited Construction Details (version 1.0).

(1) Flexible approaches on existing buildings are given in the Technical Handbooks.

8 Risk of condensation

Surface condensation



8.1 External walls will adequately limit the risk of surface condensation. Openings in walls and junctions with other elements, designed in accordance with the relevant guidance given in section 11, will also be acceptable.

Interstitial condensation

8.2 Subject to the construction used and amount of vapour being produced, the risk of interstitial condensation will be minimal. Any vapour build-up will be low and will dissipate during the summer months. Therefore, a vapour check is not required. For the purposes of calculating condensation risk a water vapour resistance factor (μ) of 60, in accordance with BS EN 12524 : 2000, may be taken for the EPS.

9 Behaviour in relation to fire



9.1 The Firewall system elements must be used in the construction of separating walls. The provisions set out in sections 9.7 and 9.8 should be taken into account when using the Standard system elements (ie with EPS webs).



9.2 The formwork elements are combustible. For buildings in Scotland, completed walls with appropriate finishes can satisfy the required durations of fire resistance and, therefore, may be used in separating walls. Where external walls are one metre or less from a relevant boundary, the construction should comply with the relevant exceptions on the use of combustible materials permitted by the guidance supporting the Building Regulations in Scotland.



9.3 EPS is combustible so the risk of fire spread over the internal wall surface will depend on the finishes that are used and the relevant requirements of the national Building Regulations should be observed.

9.4 Where the system is used as part of a cavity wall construction; to limit the risk of fire spread between floors in buildings subject to the Building Regulations, fire barriers should be installed at each floor level above the first floor (ie starting at the second storey). Fire barriers should completely seal the cavity and be chased fully into the outer formwork.

9.5 Care should be taken to ensure that all detailing at junctions, including external wall/separating wall junctions and wall/floor junctions, adequately maintains the required periods of fire resistance. Any cavities formed in the completed walls or service entry points must be appropriately fire stopped and detailing around any openings provide sufficient protection to the formwork. The formwork on the interior face must be discontinuous across wall/floor junctions.

9.6 Reinforced concrete walls constructed from the Firewall system elements can be assessed in accordance with BS 8110-2 : 1985, Table 4.6. Fire resistance values for various reinforced concrete wall thicknesses formed using the elements are given in this table. Fire resistance values achievable using the systems are given in Tables 4 and 5. Alternatively, if reinforced concrete walls are designed in accordance with BS EN 1992-1-1 : 2004, fire resistance values for various concrete wall thicknesses set out in BS EN 1992-1-2 : 2004, Table 5.4, can be used, subject to cover and design load considerations. The tabulated values do not take account of any additional protection provided by the internal and external finishes.

Table 4 Fire resistant values (minutes) for minimum concrete core thickness for walls (Firewall elements only) with vertical reinforcement (BS 8110-2 only)⁽¹⁾

Reinforcement and concrete specification	Concrete thickness (mm) ⁽²⁾				
	30	60	90	180	240
Walls with less than 4% reinforcement made from dense aggregate	–	–	200	–	–
Walls with 0.4% to 1% reinforcement made from dense aggregate with 25 mm cover to reinforcement	140	140	140	200	–
Walls with over 1% reinforcement made from dense aggregate with 25 mm cover to reinforcement	140	140	140	200	200

(1) Concrete walls constructed from the formwork system have been assessed in accordance with BS 8110-2 : 1985, Table 4.6 (note: actual element core widths stated in Table 4).

(2) Excluding any combustible finish for a fire resistance (loadbearing capacity, integrity and insulation).

Table 5 Minimum concrete core thickness for loadbearing reinforced concrete walls (Firewall elements only) as per BS EN 1992-1-2 : 2004, Table 5.4

Standard fire resistance	Minimum dimensions (mm) Wall thickness/axis distance ⁽¹⁾ for:			
	$\mu_{fi}^{(2)} = 0.35$		$\mu_{fi}^{(2)} = 0.7$	
	wall exposed on one side	wall exposed on two sides	wall exposed on one side	wall exposed on two sides
REI 30	100/10 ⁽³⁾	120/10 ⁽³⁾	120/10 ⁽³⁾	120/10 ⁽³⁾
REI 60	110/10 ⁽³⁾	120/10 ⁽³⁾	130/10 ⁽³⁾	140/10 ⁽³⁾
REI 90	120/20 ⁽³⁾	140/10 ⁽³⁾	140/25 ⁽³⁾	170/25

(1) Centre of reinforcement to nearest exposed surface.

(2) The definition of μ_{fi} is given in BS EN 1992-1-1 : 2004, Section 5.3.2(3).

(3) Normally, the cover specified in BS EN 1992-1-1 : 2004 will control this distance.


9.7 Reinforced concrete walls constructed from the Standard system elements (ie with EPS webs, for use in other than separating walls), should be assessed for fire resistance in accordance with BS 8110-2 : 1985, section 4 or BS EN 1992-1-2 : 2004, section 5.3.

9.8 For unreinforced walls constructed from the Firewall system elements, acting as fire walls, the minimum thickness requirements set out in BS EN 1992-1-2 : 2004, clause 5.4.2, must be taken into account.

10 Weathertightness

Resistance to rain ingress is provided by the external finishes and has not been assessed by the BBA. Care should be taken to ensure the design and construction using the system complies with the relevant good practice described in the applicable codes and the Certificate holder's Installation procedures.

11 Damp-proofing and waterproofing

11.1  The formwork elements will not transmit moisture by capillary action. The concrete wall formed with the system should be constructed using the specified concrete recommended by the Certificate holder (see sections 1.5, 6.10 and 6.11).

11.2 Use of the system below ground to resist the effects of hydrostatic head or ground water ingress has not been assessed and is not covered by this Certificate. The recommendations given in BS 8102 : 2009 should be adopted in respect of the watertightness of the whole structure (see also section 4.3). The advice of the Certificate holder should be sought on particular applications. Where a type A or C basement construction is adopted, suitable collector drain and backfilling medium should be provided to eliminate the build up of hydrostatic head behind the wall, where required. The Certificate holder should be consulted for advice on suitable waterproofing materials and methods of waterproofing.

11.3 Window and door openings and penetrations of the concrete, such as pipe entries or formwork ties, must also be securely sealed to maintain watertightness. The advice of the Certificate holder should be sought on suitable details.

12 Proximity of flues and appliances

When installing the product in close proximity to certain flue pipes and/or heat-producing appliances, the following provisions to the national Building Regulations are acceptable:


England and Wales — Approved Document J3


Scotland — Mandatory Standards 3.18, clause 3.18.5⁽¹⁾, and 3.19, clause 3.19.4⁽¹⁾

Northern Ireland — Technical Booklet L.

(1) Technical Handbook (Domestic).


13 Airtightness

 13.1 Buildings can achieve adequate resistance to heat loss by air infiltration provided there is effective sealing around junctions between units during site assembly. Care should be taken to ensure that junctions with other elements and openings comply with the relevant guidance for airtightness as given in the relevant documents referred to in section 7.4.


 13.2 In England, Wales and Northern Ireland, completed buildings are subject to pre-completion testing for airtightness in accordance with the requirements of:

England and Wales — Approved Document L1A (section 43) L2A (section 20B)


Northern Ireland — Technical Booklets F1 (Sections 2.59 to 2.69) and F2 (Sections 2.72 to 2.77).

 13.3 In Scotland, completed dwellings are subject to testing air permeability in accordance with the requirements of Mandatory Standard 6.2 (clause 6.2.5). Alternatively, where a default design value of $15 \text{ m}^3 \cdot \text{m}^{-2} \cdot \text{h}^{-1}$ at 50 Pa is stated in demonstrating compliance under Mandatory Standard 6.1, testing is not required.


14 Sound insulation

 14.1 In England and Wales, separating walls are subject to pre-completion testing in accordance with Approved Document E, Section 1. A similar approach is described in the Scottish Building Standards, section 5.1.2⁽¹⁾ and the Building Regulations (Northern Ireland), Document G.


14.2 Internal walls and walls flanking separating walls in new dwellings and rooms for residential purposes should have a minimum mass per unit area, excluding finishes, in excess of $120 \text{ kg} \cdot \text{m}^{-2}$.

 14.3 Separating walls with a concrete core density greater than $2200 \text{ kg} \cdot \text{m}^{-3}$ and thickness of 200 mm, will achieve a minimum mass per unit area for the core of $415 \text{ kg} \cdot \text{m}^{-2}$ and can contribute to providing the requirements of Approved Document E, Section 2.

15 Maintenance and repair

 Minor repairs to the formwork can be carried out prior to concrete pouring using expanded foam, to reduce leakage of wet concrete and maintain the thermal integrity of the EPS.

16 Durability

 Concrete walls constructed with the system will have a service life of not less than 60 years provided they are designed in accordance with section 6. The formwork system elements will have a similar service life provided it is protected from damage by the external and internal finishes of the wall construction (constituting a 'mild' exposure environment) and these are adequately maintained.

Installation

17 General

17.1 Installation of the Beco Wallform Insulating Concrete Formwork System is carried out in accordance with the Certificate holder's installation instructions, by trained, approved or supervised operatives and the requirements of BS 5975 : 2008 and BS 8000-2.1 : 1990. Continuous supervision during placing and compacting of the concrete must be provided. Where required, the formwork elements can be cut using conventional woodworking tools.

17.2 Attention is drawn to the need for accurate levelling of the foundation and initial setting out of adjustments to be made.

17.3 In general, concrete should be placed by line pump and nozzle although small quantities of concrete (e.g. to window sills), can be placed by hand. As an alternative, crane and skip can be employed.

17.4 Concrete must be compacted in accordance with the requirements of BS EN 1992-1-1 ; 2004 or BS 8110-1 : 1997. Concrete placement must not exceed a flow rate of $12 \text{ m}^3 \cdot \text{h}^{-1}$ in passes not exceeding 0.5 metre in height for reinforced concrete and 0.9 metre in height for unreinforced walls. The total daily pour height must not exceed 3 metres.

17.5 For unreinforced walls, compaction of the concrete by hand tamping or rodding is adequate. For reinforced walls mechanical compaction should be employed, using external pad or poker vibrators not exceeding 25 mm diameter as the formwork elements are easily damaged.

17.6 Where required, additional reinforcement can be placed within the system and quantities are dependent on design and detail requirements (see section 6). Horizontal reinforcement can be placed in different locations across the concrete fill void using the EPS webs or wire ties as temporary support. Vertical reinforcement can be placed against the horizontal reinforcement and secured using standard fixing methods. Bar lapping lengths in accordance with BS EN 1992-1-1 : 2004 or BS 8110-1 : 1997 should be adopted. All reinforcement should be accurately positioned to ensure that the minimum required cover to the concrete is provided. Starter or dowel bars may be recommended depending on reinforcement requirements or engineer's specification. Ties should not be cut or modified when locating reinforcement. The use of steel fibres as an alternative to standard reinforcement (bar or mesh) has not been assessed by the BBA. If used it must be subject to approval of the person responsible in the building design.

17.7 The concrete can be placed in freezing conditions as it will be thermally protected by insulation provided by the formwork, although the temperature of the concrete being placed must be between 5°C and 30°C. In air temperatures below 5°C or temperatures above 25°C the top of the formwork should be protected to aid curing after completion of concreting.

17.8 Suitably durable and mechanically adequate fixings, reinforcing starter bars or support brackets must be used for all structural elements, eg floors and roofs (see Figure 2), and must be post-drilled or cast into the concrete core. The EPS elements must not be used as a structural medium.

Figure 2 Typical installation





Figure 2 Typical installation (continued)



18 Preparation

18.1 The preparation, installation and temporary support of the formwork system must be in accordance with the Certificate holder's installation instructions.

18.2 The foundation must be level, smooth finished, cleaned off and within a tolerance of ± 10 mm in any direction. Any out-of-tolerances must be made good prior to placement of formwork.

18.3 When stepped foundations are required, 250 mm steps should be provided wherever possible to minimise cutting of forms and wastage.

19 Procedure

Wall assembly

19.1 Prior to the damp proof course being laid, a line of the wall to be built is first checked.

19.2 Starting at the corners and working into the centre point of each wall, the formwork elements are pushed firmly together using a stretcher bond format.

19.3 Depending on the footing detail required, the following and subsequent courses are then built up (ensuring that vertical joints do not coincide). End pieces are inserted into any opening sides as erection of the formwork proceeds as should any reinforcement required for structural design purposes.

19.4 Where the specified storey height is not a multiple of 250 mm, height adjusters may increase height in increments of 62.5 mm, or alternatively, the formwork can be cut to suit.

19.5 Window and door openings (see Figure 2) are formed and trimmed during construction of the formwork and framed using specific formwork lintel elements and end pieces. Openings should be made slightly undersize, then trimmed after the concrete has been cured to obtain an accurate opening size and avoid the need for supplementary packing. All openings and lintels formed as part of the construction works must be adequately braced and supported until the concrete has attained its minimum design strength.

19.6 It is essential that effective bracing and propping of walls takes place during construction to ensure stability, level, straightness and plumb of walls. The Certificate holder can advise on the provision of propping systems.

19.7 As a minimum, the full height of the assembled formwork must be supported at corners and along the wall lengths with bracings at a maximum 1.5 metre centres. As the rigidity of the formwork is reduced by openings, additional bracing and propping must be introduced to maintain stability during concrete pouring.

Concrete placement

19.8 Prior to concrete pouring, a check is carried out on the system to ensure conformity to design and layout, correct alignment and plumb, and that bracings and props are secured. Reinforcement should be checked for correct cover distance and rigidity. Where reinforcement is only provided above openings, the individual bars should extend at least 500 mm beyond the opening span.

19.9 For concrete pumping, line diameter at point of delivery should be 100 mm using a flexible end hose and concreting nozzle. The concrete pumping rate should be such that excessive pressure is not allowed to occur, both for the safety of the site operative and to avoid damage to the formwork. The stream of concrete should be aimed directly into the void and away from corners. The concrete pour height should be restricted to 500 mm for reinforced concrete and 900 mm for unreinforced concrete.

19.10 The formwork should be checked for alignment and plumb before proceeding with the next pass; this will also allow the first pour to stiffen. The next pass proceeds in the same manner until the first storey-height has been reached. At window and door openings, concrete is poured either side of each opening up to sill level and the concrete allowed to stiffen before the next pour is commenced.

19.11 When forming horizontal construction joints between concrete pours a gap of 100 mm should be left below top of formwork lifts.

Heavy wall loads

19.12 Heavy wall loads (such as structural members) should be supported by the concrete core and not the formwork elements. This can be achieved by the use of timber blocks screwed or bolted into the concrete core, or cast-in anchor bolts and metal plates.

19.13 Consideration should be given at the design stage to the positioning of damp-proof courses and gas membranes, wall fixings, service pipes and joists, relative to the position of connecting assemblies. They can be incorporated by following the manufacturer's details. Care must be taken not to damage the elements and cold bridging effects must be considered.

20 Finishing

Backfilling

20.1 Backfilling around bottom layers of formwork to the ground floor or basement walls must not take place until the concrete structure has reached sufficient design strength (as directed by the person responsible for the structural design).

Electrical and plumbing

20.2 Electrical and plumbing services can be fixed within the formwork by cutting chases into the EPS using a router, hot wire cutter or plasterboard knife. All electrical services should be ducted. Any services introduced should conform to Building Regulation and Health and Safety requirements. Further details on fixing methods can be obtained from the Certificate holder.

Wall penetrations

20.3 Sleeves for ducts or service penetrations may be positioned within the formwork prior to concrete pouring. Service entry points to basement walls should be avoided. All service entry point should be sealed to prevent ingress of water, dampness or vermin.

Internal wall finishes

20.4 A range of internal finishes can be applied or fixed directly to the system subject to fire restrictions. Where conventional dry lining systems, based on gypsum plasterboard, are used they should be screw-fixed into the concrete core.

External wall finishes

20.5 External cladding must be supported by means of a system compatible with the specified cladding and the Wallform construction. Masonry systems may be supported by wall ties cast into the concrete core of the wall; curtain wall, timber or panel claddings may be supported by batten and rail systems pinned back to the concrete core. Render Systems (described in section 1.7) can be applied directly to the EPS surface in conjunction with metal or plastic lathing and suitable fixings. Further details can be obtained from the Certificate holder.

Technical Investigations

21 Tests

Site observations were carried out in broad accordance with the requirements of ETAG 009 : 2002 as part of normal construction under site conditions. Hydrostatic pressures in excess of the restrictions imposed in this Certificate (see section 6.5) resisted the wet concrete: indicating an adequate factor of safety when installed in accordance with this Certificate. The efficiency of filling using a line pump and the overall stability of formwork due to head of wet concrete was also noted.

22 Investigations

22.1 A site visit was carried out to witness the installation process including construction of formwork, placement of reinforcement and pouring of concrete and overall performance of the formwork.

22.2 An assessment was made on technical data relating to:

- thermal performance.
- Acoustic performance
- Fire performance.

Bibliography

- BRE report 443 : 2006 *Conventions for U-value calculations*
- BS 4449 : 2005 *Steel for the reinforcement of concrete — Weldable reinforcing steel — Bar coil and decoiled product — Specification*
- BS 5975 : 2008 +A1:2011 *Code of practice for temporary works procedures and the permissible stress design of falsework*
- BS 8000-2.1 : 1990 *Workmanship on building sites — Code of practice for concrete work — Mixing and transporting concrete*
- BS 8007 : 1987 *Code of practice for design of concrete structures for retaining aqueous liquids*
- BS 8102 : 2009 *Code of practice for protection of structures against water from the ground*
- BS 8110-1 : 1997 *Structural use of concrete — Code of practice for design and construction*
- BS 8110-2 : 1985 *Structural use of concrete — Code of practice for special circumstances*
- BS 8212 : 1995 *Code of practice for dry lining and partitioning using gypsum plasterboard*
- BS 8298-1 : 2010 *Code of practice for the design and installation of natural stone cladding and lining. General*
- BS 8298-2 : 2010 *Code of practice for the design and installation of natural stone cladding and lining. Traditional handset external cladding*
- BS 8298-3 : 2010 *Code of practice for the design and installation of natural stone cladding and lining — Stone-faced pre-cast concrete cladding systems*
- BS 8500-1 : 2006 *Concrete — Complementary British Standard to BS EN 206-1. Method of specifying and guidance for the specifier*
- BS EN 206-1 : 2000 *Concrete — Specification, performance, production and conformity*
- BS EN 480-1 : 2006 *Admixtures for concrete, mortar and grout — Test methods — Reference concrete and reference mortar for testing*
- BS EN 520 : 2004 *Gypsum plasterboards — Definitions, requirements and test methods*
- BS EN 602 : 2004 *Aluminium and aluminium alloys — Wrought products — Chemical composition of semi-finished products used for the fabrication of articles for use in contact with foodstuff*
- BS EN 826 : 1996 *Thermal insulating products for building applications — Determination of compression behaviour*
- BS EN 845-1 : 2003 *Specification for ancillary components for masonry — Ties, tension straps, hangers and brackets*
- BS EN 934-2 : 2001 *Admixtures for concrete, mortar and grout — Concrete admixtures — Definitions and requirements, conformity, marking and labelling*
- BS EN 1991-1-4 : 2004 *Eurocode 1 : Actions on structures — General actions — Wind actions*
- BS EN 1992-1-1 : 2004 *Eurocode 2 : Design of concrete structures — General rules and rules for buildings*
- BS EN 1992-1-2 : 2004 *Eurocode 2 : Design of concrete structures — General rules and rules for buildings. General rules. Structural fire design*
- BS EN 1996-1-2 : 2005 *Eurocode 6 : Design of masonry structures — General rules — Structural fire design*
- BS EN 12089 : 1997 *Thermal insulating products for building applications — Determination of bending behaviour*
- BS EN 12350-2 : 2000 *Testing fresh concrete — Slump test*
- BS EN 12524 : 2000 *Building materials and products — Hygrothermal properties — Tabulated design values*
- BS EN 12667 : 2001 *Thermal performance of building materials and products — Determination of thermal resistance by means of guarded hot plate and heat flow meter methods — Products of high and medium thermal resistance*
- BS EN 13914-1 : 2005 *Design, preparation and application of external rendering and internal plastering — External rendering*
- BS EN ISO 6946 : 1997 *Building components and building elements — Thermal resistance and thermal transmittance — Calculation method*
- ETAG 009 : 2002 *Non Loadbearing permanent shuttering kit/systems based on hollow blocks or panels of insulating materials and sometimes concrete*

23 Conditions

23.1 This Certificate:

- relates only to the product/system that is named and described on the front page
- is issued only to the company, firm, organisation or person named on the front page — no other company, firm, organisation or person may hold or claim that this Certificate has been issued to them
- is valid only within the UK
- has to be read, considered and used as a whole document — it may be misleading and will be incomplete to be selective
- is copyright of the BBA
- is subject to English Law.

23.2 Publications, documents, specifications, legislation, regulations, standards and the like referenced in this Certificate are those that were current and/or deemed relevant by the BBA at the date of issue or reissue of this Certificate.

23.3 This Certificate will remain valid for an unlimited period provided that the product/system and its manufacture and/or fabrication, including all related and relevant parts and processes thereof:

- are maintained at or above the levels which have been assessed and found to be satisfactory by the BBA
- continue to be checked as and when deemed appropriate by the BBA under arrangements that it will determine
- are reviewed by the BBA as and when it considers appropriate.

23.4 The BBA has used due skill, care and diligence in preparing this Certificate, but no warranty is provided.

23.5 In issuing this Certificate, the BBA is not responsible and is excluded from any liability to any company, firm, organisation or person, for any matters arising directly or indirectly from:

- the presence or absence of any patent, intellectual property or similar rights subsisting in the product/system or any other product/system
- the right of the Certificate holder to manufacture, supply, install, maintain or market the product/system
- actual installations of the product/system, including their nature, design, methods, performance, workmanship and maintenance
- any works and constructions in which the product/system is installed, including their nature, design, methods, performance, workmanship and maintenance
- any loss or damage, including personal injury, howsoever caused by the product/system, including its manufacture, supply, installation, use, maintenance and removal
- any claims by the manufacturer relating to CE marking.

23.6 Any information relating to the manufacture, supply, installation, use, maintenance and removal of this product/system which is contained or referred to in this Certificate is the minimum required to be met when the product/system is manufactured, supplied, installed, used, maintained and removed. It does not purport in any way to restate the requirements of the Health and Safety at Work etc. Act 1974, or of any other statutory, common law or other duty which may exist at the date of issue or reissue of this Certificate; nor is conformity with such information to be taken as satisfying the requirements of the 1974 Act or of any statutory, common law or other duty of care.